

Building a Teddington



The hull is laid up.



Tanks/seats are made with marine ply BS Standard 1088 and sheathed with fibreglass.



The keel is filled with timber and resin to prevent any leaks from wear and tear to the keel.



The tank seats are installed.



The interior is flocoted.



Installation of the teak woodwork begins.



Bow plate installed using West System epoxy and marine grade 316 stainless steel fasteners.



Teak transom plate.



Gunnels glued on using epoxy and a few clamps.



Nearly finished!

